

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
301 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-02-3-117

15.159.00508-00-01  
API NUMBER Aug. 31, 1979

LEASE NAME Scott O'WWD <sup>KCC</sup> <sub>8/27-19/04</sub>

RECEIVED

JUN 15 2004

KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1  
330 Ft. from <sup>N</sup> Section Line  
330 Ft. from <sup>W</sup> Section Line

LEASE OPERATOR CORONADO OIL & GAS, INC.

SEC. 16 TWP. 19 RGE. 6W (E) or (W)

ADDRESS P.O. Box 1285 Great Bend, Kansas 67530

COUNTY Rice

PHONE# (620) 792-6702 OPERATORS LICENSE NO. 6141

Date Well Completed \_\_\_\_\_

Character of Well Oil

Plugging Commenced 6-8-04

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

Plugging Completed 6-9-04

The plugging proposal was approved on \_\_\_\_\_ (date)

by Mike Wilson (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. 3263'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	200'	None
				4-1/2"	3263'	2400'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each set.  
Plugged off bottom with sand to 3000' and 4 sacks cement. Cut casing loose @2400', pulled up to 900', pumped 35 sacks cement with 200# hulls, pulled up to 550', pumped 35 sacks cement pulled up to 250', pumped 100 sacks cement and circulated to surface. 60/40 pos. 4% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Coronado Oil & Gas, Inc.

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)  
of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 14th day of June, 20 04

[Signature]  
Notary Public

My Commission Expires: \_\_\_\_\_

NOTARY PUBLIC - State of Kansas  
IRENE HERZBERG  
My Appt. Exp. 8-24-05

Form CP  
Revised 05-