

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

15-153-20183-00-00

OCT 3 1974

CONSERVATION DIVISION
Wichita, Kansas

10-3-74

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Abercrombie Drilling, Incorporated,

Complete Address 801 Union Center, Wichita, Kansas.

Lease Name Headrick Well No. 1

Location CSW-NW Sec. 17 Twp. 2 Rge. (E) (W) 35

County Rawlins Total Depth 4915'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Ks. License No. _____

Operation Completed: Hour 12:00 M Day 1 Month 10 Year 1974

The above well was plugged as follows:

334'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 2000'.

Circulated hole with heavy mud. Pulled DP to 2225' and displaced 110 Cu. Ft. cement
thru DP from 2225' to 1900'. Pulled DP to 340' and displaced 30 Cu. Ft. cement thru
DP from 340' to 265'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Dolek
Well Plugging Supervisor

INVOICED

DATE 10/4/74
INV. NO. 32-W