

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-153-20,720 ⁰⁰⁻⁰⁰

LEASE NAME Bernice Headrick

WELL NUMBER 1

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 19 TWP. 2 RGE. 35W (E) or (W)

COUNTY Rawlins

Date Well Completed 8-19-88

Plugging Commenced 8-19-88

Plugging Completed 8-19-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Glen S. Soderstrom

ADDRESS 8700 Stemmons Frwy. Ste. 311, Dallas, TX 75247

PHONE#(214) 634-0425 OPERATORS LICENSE NO. 3555

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Hays

Is ACO-1 filed? Attached If not, is well log attached? Well log is attached

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4800'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From Surf.	To	Size	Put in	Pulled out
	<u>8-25-88</u>		<u>350</u>	<u>8 5/8 20#</u>	<u>348'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Cement of 60/40 Poz, 6% gel used. 1st plug 3180'-3130' w/25 sks. 2nd plug @ 2200'-2120' w/100 sks. 3rd plug @ 400'-300' w/40 sks. 8 5/8" plug @ 60' to surface w/10 sks. Rathole plugged w/10 sks and mousehole plugged w/15 sks.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. N/A

Address P. O. Box 31 Russell, Kansas 67665

STATE OF Texas COUNTY OF Dallas, ss.

Glen S. Soderstrom, Operator

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 8700 Stemmons Frwy. Ste. 311 Dallas, TX 75247

SUBSCRIBED AND SWORN TO before me this 24th day of August, 19 88

Rosemary Soderstrom
Notary Public

Expires: July 29, 1992

