

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-153-20291 *0001*

LEASE NAME Frisbie

WELL NUMBER #3 SWD

SPOT LOCATION 70' EWL 500' SNL
SW/4

SEC. 18 TWP. 2S RGE. 35 (E) or (W)

COUNTY Rawlins

Date Well Completed 7/22/77

Plugging Commenced 8/5/88

Plugging Completed 8/5/88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Murfin Drilling Company
250 N. Water, Suite 300
ADDRESS Wichita, Ks 67202

PHONE # (316) 267-3241 OPERATORS LICENSE NO. 6033

Character of Well SWD
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? Hays, Ks

Is ACO-1 filed? no If not, is well log attached? yes

Producing formation Cedar Hills Depth to top 2811 bottom 3110 T.D. 3180

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|------|-------|--------|------------|
| | | 0 | 350 | 8 5/8 | 350 | -0- |
| | | 0 | 3179 | 4 1/2 | 3179 | -0- |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Retrievable bridge plug @ 2465' w/2 sx sand on top. 200 sx Common f/370-461'. 8/5/88 - Ran tbg to 540' (outside csg f/370-540'). Loaded hole w/50 sx Common cmt w/1/4#/sx Flocele. Pulled tbg. Pumped 150 sx Common w/1/4#/sx Flocele followed by 230 sx 60-40 Poz w/2% gel. Max pressure 1200 psig. Well plugged @ 2:23 PM 8/5/88.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Company License No. 6033
Address 250 N. Water, Suite 300 Wichita, Ks 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Larry M. Jack, Production Manager (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) By: Larry M Jack

(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 7 day of Sept., 1988

Kerran Redington
Notary Public
Kerran Redington

My Commission expires: 2/6/90

WELL LOG

COMPANY Murfin Drilling

SEC. 18 T. 2S R. 35W
LOC. SW/4

FARM FRISBIE NO. 3W


RIG. NO. 3

TOTAL DEPTH 3180'

COUNTY Rawlins
KANSAS

COMM. 7/6/77

COMP. 7/9/77



CONTRACTOR Murfin Drilling

CASINO

20 10
15 8 5/8" @ 359' w/250 sx
12 6
13 5
4 1/2" @ 3179' w/400 sx

ELEVATION

PRODUCTION SWD

FIGURES INDICATE BOTTOM OF FORMATIONS

| | |
|-------------|------|
| sand, clay | 305 |
| shale | 1380 |
| shale, sand | 2295 |
| shale | 2565 |
| shale, sand | 3153 |
| Anhy | 3180 |
| RTD | 3180 |

RECEIVED
STATE CORPORATION COMMISSION
SEP - 8 1988
CONSERVATION DIVISION
Wichita, Kansas


State of Kansas
County of Sedgwick } ss:

I, Wm. S. Shropshire of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Frisbie #3W (SWD) well.

Wm. S. Shropshire

Subscribed and sworn to before me this 11th day of August 1977



JOLEENE S. FRISBIE, STATE NOTARY PUBLIC
My Commission Expires: My Comm. Exp. March 13, 1979

Joleene S. Frisbie
NOTARY PUBLIC