

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
10 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-153-20232 00-00

LEASE NAME Frisbie

WELL NUMBER #1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

1820 Ft. from S Section Line

4780 Ft. from E Section Line

SEC. 18 TWP. 2S RGE. 35W (E) or (W)

COUNTY Rawlins

LEASE OPERATOR Murfin Drilling Company

ADDRESS 250 N. Water, Suite 300 Wichita, KS 67202

PHONE# 316 267-3241 OPERATORS LICENSE NO. 6033

Date Well Completed 1/14/76

Character of Well Oil

Plugging Commenced 7/28/89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8/01/89

Plugging proposal was approved on 6/89 (date)

Carl Goodrow (KCC District Agent's Name).

ACO-1 filled? NO If not, is well log attached? yes

Producing Formation LKC Depth to Top 4211 Bottom 4509 T.D. 4525

Show depth and thickness of all water, oil and gas formations.

WELL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	325'	w/325 sx
				5 1/2"	4523	w/200 sx

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
7/28/89 Perf 5 1/2" csg @ 2300-2301' w/3 shots. Pumped 100 sx Halliburton Econolite cmt w/150 lbs of cotton seed hulls dwn 8 5/8" and 5 1/2" annulus, 225 # max press; 225# ISIP. Pumped 200 sx Halliburton Econolite w/350 lbs of hulls dwn 5 1/2" csg. Max press 200#. ISIP vac. 8/1/89 Topped csg off w/50 sx of Econolite cmt.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Company License No. 6033

Address 250 N. Water, Suite 300 Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company


CITY OF KS COUNTY OF Sedgwick, ss.

Larry M. Jack, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filled that same are true and correct, so help me God.

(Signature) By: Larry M. Jack

(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 22 day of August, 19 89



Kerran Redington Notary Public  
Kerran Redington

15-153-20232-00-00

# WELL LOG

COMPANY Murfin Drilling

SEC. 18 T. 2S R. 35W  
LOC. 150' SW C NW SW

FARM FRISBIE NO. 1


RIG. NO. 14

TOTAL DEPTH 4525'

COUNTY Rawlins  
KANSAS

COMM. 12/3/75

COMP. 12/15/75



CONTRACTOR Murfin Drilling Company

### CASING

20	10
15	8 5/8" @ 325' w/325 sx
12	6
13	5 1/2" @ 4523' w/200 sx

ELEVATION 3285 GL  
3290 KB

PRODUCTION Producer

FIGURES INDICATE BOTTOM OF FORMATIONS

190 - shale  
 270 - sand  
 2770 - shale  
 2845 - shale, w/pyrite  
 3175 - shale  
 3365 - shale, Anhydrite  
 3695 - shale  
 4286 - lime, shale  
 4525 - lime  
 4525 - TD

RECEIVED  
STATE CORPORATION COMMISSION

12-18-1975

CONSERVATION DIVISION  
Wichita, Kansas

State of Kansas }  
County of Sedgwick } ss:

I, James R. Daniels of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Frisbie #1 well.

Subscribed and sworn to before me this 31st day of December 1975

JOHN S. FRISBIE, STATE NOTARY PUBLIC

My Commission Expires: My Comm. Exp. March 13, 1979

James R. Daniels  
John S. Frisbie  
NOTARY PUBLIC

