


19-153-2040600-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rawlins County. Sec. 18 Twp. 2S Rge. 35W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
C SW NW
Lease Owner West Kansas Oil Corporation
Lease Name CAHOJ #1 Well No. #1
Office Address Rt. #1, Selden, Kansas 67757
Character of Well (Completed as Oil, Gas or Dry Hole) _____
Dry Hole
Date Well completed January 22, 1981 19 81
Application for plugging filed January 22 19 81
Application for plugging approved January 22 19 81
Plugging commenced January 22 19 81
Plugging completed January 22 19 81
Reason for abandonment of well or producing formation _____
No commercial quantity of oil or gas encountered.
If a producing well is abandoned, date of last production _____
19 _____



Locate well correctly on above
Section Plat

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazar
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4569'
Show depth and thickness of all water, oil and gas formations.

| OIL, GAS OR WATER RECORDS | | | | CASING RECORD | | |
|---------------------------|---------|------|----|---------------|--------|------------|
| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

T.D. @ 4569'
Set 1st Plug @ 2000' with 70 sx.
Set 2nd Plug @ 360' with 20 sx.
Set 3rd Plug @ 40' Solid Bridge with 10 sx.
Rathole with 5 sx., 50-50 posmix.

State Plugger - Gilbert Balthazar
Plug was down @ 5:00 a.m., 1/22/81.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Vice President (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of March, 1981

Suzanne M. Hofer
Suzanne M. Hofer Notary Public.

My commission expires 2/4/85



RECEIVED
STATE CORPORATION COMMISSION

MAR 11 1981
3-11-81
CONSERVATION DIVISION
Wichita, Kansas

15-153-20406-00-00

CONTRACTOR'S WELL LOG

OPERATOR: West Kansas Oil Corporation
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: CAHOJ #1
 LOCATION: C SW NW, Section 18-2S-35W
 Rawlins County, Kansas
 SPUD DATE: 1/14/81
 COMPLETION DATE: 1/22/81

| | | |
|------|------|---------------------|
| 0 | 41 | Sand & Clay |
| 41 | .365 | Sand & Shale & Clay |
| 365 | 2495 | Shale & Sand |
| 2495 | 2538 | Shale |
| 2538 | 2865 | Shale & Sand |
| 2865 | 3175 | Shale & Anhydrite |
| 3175 | 3214 | Anhydrite |
| 3214 | 3720 | Shale |
| 3720 | 4047 | Shale & Lime |
| 4047 | 4569 | Lime & Shale |
| | 4569 | Rotary Total Depth |

Spud hole @ 3:00 p.m., 1/14/81. Drilled 365' in a 12 1/4" hole. Ran 9 jts. of 8 5/8" - 20# casing (tally @ 356.01) Set @ 364.01. Cemented with 275 sx. of 60-40 posmix, 3% c.c., 2% gel. Cement did circulate. Plug was down @ 10:30 p.m., 1/14/81. Cement by Halliburton. Drilled the plug @ 6:30 a.m., 1/15/81.

RTD @ 4569'. D&A. Set 1st Plug @ 2000' with 70 sx. Set 2nd Plug @ 360' with 20 sx. Set 3rd Plug @ 40' Solid Bridge with 10 sx. Rathole with 5 sx. Cemented with 50-50 posmix, Cement by Halliburton. State Plugger - Gilbert Balthazar. Plug was down @ 5:00 a.m., 1/22/81.

SAMPLE TOPS:
 Anhydrite 3174'
 B/Anhydrite 3215'

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the CAHOJ #1, C SW NW, Section 18-2S-25W, Rawlins County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 7th day of March, 1981.

2/4/85

Suzanne M. Hofer
 Suzanne M. Hofer, Notary Public

