

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-153-20,650-00-00

LEASE NAME Kopriva

WELL NUMBER 1

SPOT LOCATION N/2 SE NW

SEC. 13 TWP. 2 RGE. 35 (E) or (W)

COUNTY Rawlins

Date Well Completed 3-1-86

Plugging Commenced 3-1-86

Plugging Completed 3-1-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Viking Resources

ADDRESS 217 E. William, Wichita, Kansas 67202

PHONE # (316) 262-2502 OPERATORS LICENSE NO. 5011

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation N/A Depth to top _____ bottom _____ T.D. 4400

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	307	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Spotted 25 sx cement @ 3025' thru drill pipe

Spotted 100 sx cement @ 2200' thru drill pipe

Spotted 40 sx cement @ 350' thru drill pipe

Spotted 10 sx cement @ 40' thru drill pipe

Spotted 15 sx cement in rathole, Spotted 1/ sx cement in water well

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420

Address 401 East Douglas, Suite 500, Wichita, Ks. 67202


STATE OF Kansas COUNTY OF Sedgwick, ss.

Ernest Sifford (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) Ernest Sifford

(Address) 401 E. Douglas, Suite 500
Wichita, Ks. 67202

SUBSCRIBED AND SWORN TO before me this 7th day of March, 1986




My Commission expires:

David F. Jamis
Notary Public

MAR 10 1986

CONSERVATION DIVISION

Form CP-4
Revised 01-84



15-153-20650-00-02

WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Viking Resources
217 E. William
Wichita, Kansas 67202
CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,
Wichita, Ks. 67202

Lease Name Kopriva Well No. 1
Sec. 13 T. 2 R. 35W Spot N/2 SE NW
County Rawlins State Kansas Elevation

Casing Record:

Surface: 8 5/8 @ 307' with 2% gel 3% cc 200 sx.

Production: @ with sx.

Type Well: D & A Total Depth 4400'

Drilling Commenced 2-21-86 Drilling Completed 2-28-86

Formation	From	To	Tops
Cellar	0	7	
Shale	7	1738	
Sand, Shale	1738	2185	
Shale, Lime	2185	3075	
Lime, Shale	3075	3647	
Lime	3647	4400	

STATE CORPORATION COMMISSION

MAR 10 1986

3-10-86

CONSERVATION DIVISION
Wichita, Kansas