


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rawlins County. Sec. 2 Twp. 2S Rge. (E) 35 (W)
Location as "NE/CNW/SW" or footage from lines. C NW NW
Lease Owner Graves Drilling Co., Inc.
Lease Name Zadina Well No. 1
Office Address 505 Union Center Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Oct. 1, 19 69
Application for plugging filed (letter 10/6/69) Oct. 1, 19 69
Application for plugging approved Oct. 1, 19 69
Plugging commenced Oct. 1, 19 69
Plugging completed Oct. 1, 19 69
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves
Producing formation Depth to top Bottom Total Depth of Well 3165 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	261'	8-5/8"	261'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 1860 feet. Set first plug at 1860 feet with 100 sacks cement. Filled hole with heavy mud to 300 feet. Set second plug at 300 feet with 25 sacks cement. Filled hole with heavy mud to 40 feet. Set third plug at 40 feet with 10 sacks cement. Pumped cement through drill pipe with Halliburton pump truck. Job complete @ 4:00 PM, October 1, 1969.

RECEIVED
STATE CORPORATION COMMISSION
OCT 7 1969
CONSERVATION DIVISION
Wichita, Kansas


10-7-69

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Gabbert-Jones, Inc.
Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
E. E. Hall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E E Hall
830 Sutton Place, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 6 day of October, 19 69



Feb. 1, 1972
Barbara J. Layton
Barbara J. Layton Notary Public.

15-153-20058-00-00

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

RECEIVED
STATE CORPORATION COMMISSION
OCT 7 1969
CONSERVATION DIVISION
Wichita, Kansas
10-7-69

ZADINA #1
C NW NW Section 2-2S-35W
Rawlins County, Kansas

Commenced: September 27, 1969
Completed: October 1, 1969

OPERATOR - Graves Drilling Co., Inc., 505 Union Center Bldg., Wichita, Kansas 67202

DEPTH		FORMATION	REMARKS
From	To		
0	271	Top soil, sand, clay and shale	Ran 13 joints of 8-5/8" casing, set @ 261' w/225 sacks cement.
271	2105	Shale and sand	
2105	2320	Shale	
2320	2620	Shale and lime	
2620	2665	Sand	
2665	2835	Shale and lime	
2835	3076	Shale, shells w/red bed	
3076	3114	Anhydrite	
3114	3165	Shale	
3165	TD		Dry and abandoned.

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the C NW NW Section 2-2S-35W, Rawlins County, Kansas, to the best of my knowledge and belief.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 6 day of October, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972.

Barbara J. Layton
Barbara J. Layton, Notary Public

