


15-153-00052-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rawlins County. Sec. 1 Twp. 2S Rge. 35W (E) (W)
Location as "NE/CNW/SW" or footage from lines SE SE NE
Lease Owner Imperial Oil of Kansas, Inc.
Lease Name Skolout Well No. 1
Office Address 780 Fourth National Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 1, 1959
Application for plugging filed December 1, 1959
Application for plugging approved December 1, 1959
Plugging commenced December 1, 1959
Plugging completed December 1, 1959
Reason for abandonment of well or producing formation No commercial quantities of oil found.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4947 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	322'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set No. 1 Plug at 550' with 15 sacks of cement; Set second plug at 350' with 15 sacks cement -- top plug at 40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 20 1960
CONSERVATION DIVISION
Wichita, Kansas
1-20-60

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Imperial Oil of Kansas, Inc.
Address 780 Fourth National Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Raymond L. Bacon (employee of ~~owner~~ or ~~operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.
(Signature) BY: Raymond L. Bacon V-P
780 Fourth National Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of December, 19 59
Merna L. Latier
My commission expires July 7, 1962 Notary Public.



15-153-00052 -00-00

DRILLER'S LOG

RECEIVED
STATE CORPORATION COMMISSION

JAN 20 1960

CONSERVATION DIVISION
Wichita, Kansas

1-20-60

Imperial Oil of Kansas, Inc.
780 Fourth National Building
Wichita 2, Kansas

Skolout No. 1
SE SE NE Sec. 1-2S-35W
Rawlins County, Kansas

Total Depth: 4947'

Commenced: 11-17-59 Completed: 12-1-59

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Elevation: 3197' R.B.
Production: D & A

Casing Record: Set 8-5/8" Surface Pipe at 322' with 225 sacks cement.

Figures indicate bottom of formations:

Surface Sand & Shale	322'
Shale, Shells & Sand	425'
Shale & Shells	1536'
Shale	2520'
Shale & Sand	2855'
Anhydrite	3077'
Shale	3465'
Shale & Lime	3995'
Lime	4474'
Lime & Shale	4590'
Lime	4640'
Lime & Shale	4649'
Cherokee sand	4673'
Shale & Sand	4795'
Lime & Shale	4802'
Lime & Chert	4828'
Mississippi lime & shale	4896'
Arbuckle	4947'
Total Depth	4947'

TOPS

Admire	3725'	(- 528)
Topeka	3934'	(- 737)
Oread	4034'	(- 837)
Heebner	4081'	(- 884)
Lansing	4130'	(- 933)
Base Kansas City	4395'	(-1198)
Marmaton	4429'	(-1232)
Cherokee	4564'	(-1367)
Mississippi	4787'	(-1590)
Arbuckle	4899'	(-1702)
Rotary Total Depth	4947'	(-1750)

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: *M. B. ...*
Vice-President

Subscribed and sworn to before me this 24th day of December, 1959.

My Commission expires:

July 7, 1962

Mona L. Latier
Mona L. Latier-Notary Public