



15-153-20144-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 4 - 1972
CONSERVATION DIVISION
Wichita, Kansas
12-4-72

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ralph Niernberger of Murfin Drilling Company has this
date requested permission to plug the following described well:

Mr. Niernberger guarantees payment of the plugging fee.

Operator's full Name: Buttes Gas & Oil Company,

Complete Address: 1776 Lincoln Street, Denver, Colorado.

Lease Name: August Martin Well No. 1

Location: CNE-SW Sec. 23 Twp. 2 Rge. (E)(W) 32

County: Rawlins Total Depth 4050' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Niernberger was instructed to plug the well as follows:

205'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1675'.

Circulate hole with heavy mud. Pull DP to 1900' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 215' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

H. J. Nichols
Conservation Division Agent