



15-153-20129-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. WICHITA, KANSAS 67202

RECEIVED
CONSERVATION COMMISSION
SEP 10 1971
CONSERVATION DIVISION
Wichita, Kansas

12-10-71

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jerry Nestlerode of Chief Drilling Company, Inc., has this date requested permission to plug the following described well:

Mr. Nestlerode guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Incorporated, & National Oil Co.,

Complete Address: Suite 905, Century Plaza, Wichita, Kansas.

Lease Name: Goetl Well No. 1

Location: SE-SW-NW Sec. 4 Twp. 2 Rge. (E)(W) 32

County: Rawlins Total Depth 4075' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Nestlerode was instructed to plug the well as follows:

272'--8 5/8" Surface casing, cement circulated.

Top of Dakota section @ 1750'.

Circulate hole with heavy mud. Pull DP to 1975' and displace 110 Cu. Ft. cement thru DP. Pull DP to 310' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent