



15-153-20109-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 5 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
4-5-71

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Sixbury of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Sixbury guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company,

Complete Address: 617 Union Center Building, Wichita, Kansas.

Lease Name: Pitner Well No. 1

Location: CNW-SE Sec. 11 Twp. 2 Rge. (E)(W) 32

County: Rawlins Total Depth 3945' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Sixbury was instructed to plug the well as follows:

117'--8 5/8" Surface casing, cement circulated with 110 Sx.  
Top of Dakota section @ 1625'.

Circulate hole with heavy mud. Pull DP to 1850' and displace 100 Sx.  
cement thru DP. Pull DP to 125' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent