



15-153-20095-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

OCT 26 1970

CONSERVATION DIVISION
Wichita, Kansas

10-26-70

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Walter Oden of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Oden guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Company, Incorporated,

Complete Address: 410 Fourth National Bank Building, Wichita, Kansas.

Lease Name: Lettera Lettera Well No. 1

Location: CSE-SW Sec. 11 Twp. 2 Rge. (E)(W) 32

County: Rawlins Total Depth 3883' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Oden was instructed to plug the well as follows:

266'--8 5/8" Surface casing cement circulated.
Top of Dakota section @ 1475'.

Circulate hole with heavy mud. Pull DP to 1750' and displace 100 Sx. cement thru DP. Pull DP to 275' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent