

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20163-00-00

RECEIVED
STATE CORPORATION COMMISSION

OCT 2 1973

CONSERVATION DIVISION
Wichita, Kansas

16-2-73

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Empire Drilling Company,

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Lewis Well No. C-1

Location App:-NE-NE-SW Sec. 32 Twp. 2 Rge. (E) (W)33

County Rawlins Total Depth 4125'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 4:00 PM Day 28 Month 9 Year 1973

The above well was plugged as follows:

207'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1700'.

Circulated hole with heavy mud. Pulled DP to 1925' and displaced 110 Cu. Ft. cement
thru DP from 1925' to 1600'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar..

I hereby certify that the above well was plugged as herein stated.

NOTICED

DATE 10-2-73

Signed: W. L. Dehler
Well Plugging Supervisor

INV. NO. 7970-W