

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-153-20265-00-00  
Spot: NWNW Sec/Twnshp/Rge: 29-2S-35W  
4550 feet from S Section Line, 4550 feet from E Section Line  
Lease/Unit Name: SEBERGER Well Number: 1  
County: RAWLINS Total Vertical Depth: 4794 feet

Operator License No.: 5474 Conductor Pipe: Size feet:  
Operator Name: NORTHERN LIGHTS OIL COMPAN Surface Casing: Size 8.62 feet: 377 235 SX CMT  
Address: PO BOX 164 Production: Size 5.5 feet: 4788 200 SX CMT  
ANDOVER, KS 67002 Liner: Size feet: 155.81

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/30/2000 10:00 AM  
Plug Co. License No.: 5474 Plug Co. Name: NORTHERN LIGHTS OIL COMPANY, LLC  
Proposal Rcvd. from: JEROMY SIS Company: NORTHERN LIGHTS OIL COMPAN Phone: (316) 733-1515

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations Partially Witnessed  
Date/Time Plugging Completed: 11/30/2000 11:00 AM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 377' w/235 sxs cwc.  
5 1/2" set at 4788 w/200 sxs.  
Prod. Perf 4240' - 4275'.  
Exempt area.  
Squeezed 5 1/2" w/280 sxs cement blend with 500# hulls mixed in - no pressure.  
Squeezed 8 5/8" annulus with 50 sxs cement blend - no pressure. Held.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 13 2000  
12-13-2000  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY. SPOT LOCATION READS AS FOLLOWS: 150' SE/C. NWNW 29-02-35W.

Plugged through: CSG

District: 04

AD

Signed

Carl Goodrow

(TECHNICIAN)

INVOICED  
DATE 12/13/00

2001061122

Form CP-2/3

DEC 05 2000

MURFIN DRLG. CO.  
617 UNION CENTER  
WICHITA, KS.

#1 SEBERGER

29-2-35W  
150'SE, C NW NW

CONTR MURFIN DRLG. CO.

CTY RAM INS

GEOL

FIELD WC-SEBERGER DISC.

E 3267 KB CM 9/28/76 CARD ISSUED 1/27/77 IP P 155 BOPD N/W  
LKC 4240-4275 OA

+	+	+
+	+	+
+	+	+

API 15-153-20,265

LOG	TOPS	DEPTH	DATUM
ANH	3107	+ 160	
B ANH	3143	+ 124	
TOP	3988	- 721	
OREAD	4086	- 819	
DOUG	4148	- 881	
LKC	4181	- 914	
BKG	4472	-1205	
RTD	4790	-1523	
LTD	4794	-1527	

8-5/8" 377/235sx, 5 1/2" 4788/200sx  
DST (1) 4163-4204/30-30-30-30, 65' socm  
SIP 681-669# FP 50-75# BHT 130°  
DST (2) 4244-57/45-45-30-45, 320'M w/  
SSO, SIP 1357-1345# FP 188-200#  
DST (3) 4200-57/30-45-30-45, 570' GIP,  
1710'MGO (GR 33°), SIP 1297-1273#  
FP 548-729#  
DST (4) 4271-4304/30-45-30-45, 480'MO,  
SIP 1092-995# FP 50-225#  
DST (5) 4304-20/30-45-30-45, 2970'SW,  
SIP 1406-1406# FP 500-1406# BHT 144°  
DST (6) 4316-52/45-45-30-45, 90'WM,  
SIP 1309-1273# FP 38-75# BHT 144°  
DST (7) 4350-4400/45-45-30-45, 60'M,  
SIP 1357-1333# FP 50-63# BHT 144°

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS