

6 050004

8-19

351

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 153-20,720-0000-1000

C NW SE SEC. 19, T 2 S, R 35 W/E
1980 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3555

Lease Name Bernice Hendricks # 1

Operator: Glen S. Soderstrom
Name & Address: 8700 Stemmons Frwy
Suite 311
Dallas, Texas 75247

County Rawlins 156.00
Well Total Depth 4800 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Golden Eagle Drilling License Number 8682

Address McCook, Nebraska 69001

Company to plug at: Hour: Day: 18 Month: Aug Year: 19 88

Plugging proposal received from Dave Paschall

(company name) Golden Eagle Drilling (phone)

were: Order 205 sks 60/40 Poz 6% Gel 3% Ca Cl 1 sk F.C. and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs with good circulation and no fluid loss.

Plugging Proposal Received by Bruce D. Basye (TECHNICIAN) x

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 4:00PM Day: 19 Month: August Year: 19 88

ACTUAL PLUGGING REPORT

- 1st plug at 3180' w/25 sks Anhy
- 2nd plug 2300' w/100 sks w/F.C. Dakota
- 3rd plug at 400' w/40 sks
- 4th plug at 40' w/10 sks
- 15 sks in rathole 15 sks in mousehole

Remarks: Allied Cement
(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

DATE 9-8-88

INV. NO. 22171

Signed Bruce D. Basye (TECHNICIAN) Bruce Basye

RECEIVED STATE CORPORATION COMMISSION SEP - 6 1988

9-6-88