

8-5-88

031145

-00-01

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 153-20,291 SW \_\_\_\_\_, SEC. 18, T 2 S, R 35 W/E

2140 feet from S section line  
5210 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Frisbie Well # 3 SWD

Operator: Murfin Drilling Co.

County Rawlins 103.35

Name & Address 617 Union Center

Well Total Depth 3180 feet

Wichita, Ks. 67202

Conductor Pipe: Size \_\_\_\_\_ feet

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA, KANSAS  
AUG 30 1988

Surface Casing: Size 8 5/8 feet 350

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well  D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton License Number \_\_\_\_\_

Address Oberlin, Ks.

Company to plug at: Hour: \_\_\_\_\_ Day: 5 Month: August Year: 19 88

Plugging proposal received from Terry Richardson Mike Ward and Don Butcher

(company name) Murfin Drilling and KCC Con Div. Supervisor. (phone) \_\_\_\_\_

were: 8 5/8" set at 350' w/225 sks cwc. 4 1/2" set at 3179' in Anhydrite w/400 sks Toc.

ext at 460'. Recovered 79 joints 2 3/8" tubing and 4 1/2" packer. 4 1/2" casing bad from 369' to

469' to 461' set RBP at 2465' w/2 sks sand, tested pipe below 461' to 1500#. Squeezed bad

section with 200 sks Common with wiper plug pushed to 330'. Drilled cement to 370' and

drilled out of 4 1/2" casing to 565' in shale. Ordered 200 sks Common Cement w/1/4" F.C. and 150

sks 60/40 Poz 2% Gel. Halliburton Cement Co. Webbs Water Trucks. Plugging Proposal Received by Carl Goodrow

(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:30PM Day: 5 Month: August Year: 19 88

ACTUAL PLUGGING REPORT Ran tubing to 541'. Pumped Common Cement through tubing to load

hole 50 sks. Lay down tubing, tie onto 4 1/2" casing. Squeeze w/150 sks Common Cement to 1200#

Blew off head, repair head. Finish squeeze w/230 sks 60/40 Poz 2% Gel to max Psi 1200#.

Close in Psi 300#. Plug complete.

Remarks: \_\_\_\_\_

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-31-88

Signed Carl Goodrow (TECHNICIAN)

DB

INV. NO. 22067