

6031275

7-28

API NUMBER 15-153-20232-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

150' SW of \_\_\_\_\_, SEC. 18, T. 2 S, R. 35 W & E  
C NW SW \_\_\_\_\_  
1874 feet from S section line  
4514 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033  
Operator: Murfin Drilling Co.  
Name & Address: 250 N. Water Ste 300  
Wichita, Ks. 67202

Lease Name Erishie Well # 1  
County Rawlins 147.06  
Well Total Depth 4525 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 set 325

Abandoned Oil Well \_\_\_\_\_ X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton License Number \_\_\_\_\_

Address Oberlin Ks.

Company to plug at: Hour: AM Day: 28 Month: July Year: 19 89

Plugging proposal received from John Turner

(company name) Murfin (phone) \_\_\_\_\_

were: 8 5/8" set at 325' w/325 sks. 5 1/2" set at 4523' w/200 sks. PBTD 4485'.

Perf 4271' - 4420'. Shots at 2300' Below Dakota. Order 350 sks 65/35 poz 10% gel 500# hulls. Halliburton Cement Co. Company water trucks.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:00 AM Day: 28 Month: July Year: 19 89

ACTUAL PLUGGING REPORT Squeezed 5 1/2" casing w/250 sks cement blend w/350# hulls mixed into max 300# psi. Close in 150# psi. Squeezed 8 5/8" w/100 sks cement blend w/150# hulls mixed into max psi 300#. Close in psi 150#. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 14 1989 8-14-89

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of \_\_\_\_\_)

INVOICED  
I ( ) ~~will~~ ~~not~~ observe this plugging.

DATE 8-17-89

INV. NO. 25664

*Erishie*

Signed Carl Goodrow  
(TECHNICIAN)  
Carl Goodrow