

1-3-92

58
R

4- 070975

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-153-20,785-00-00

C W2 SE /4 SEC. 24, 02 S, 32 W
1320 feet from S section line
1980 feet from E section line

Operator license# 6785 Lease Erickson well #10A-24

Operator: Schulein Company County Rawlins

Address: 1776 Lincoln St. #811 Well total depth 4035 feet ^{131.13}
Denver, Colorado 80203 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 266 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Golden Eagle Drilling, Inc. License# -

Address: 1111 East, H.P.O. Box 55, McCook, Neb. 69001

Company to plug at: Hour: A.M. Day: 3 Month: January Year: 92

Plugging proposal received from: Dave Paschall

Company: Golden Eagle Drilling, Inc. Phone: 308-345-3839

Were: 8 5/8" - 266' S.P. cwc w/165 sx. 60/40 pozmix - 6% gel. - 3% c.c. By Allied Cement. N.C. well - Elev. 2831' - Anhy. 2586. No circulation problems. Mud condition 50 vis. - 9.1 weight. 7 water loss. Proposal 200 sx. 60/40 pozmix - 6% gel - 3% c.c. and 1 sx. F.C. Circulate hole - Spot with drill stem, heavy mud between all plugs. 25 sx. @ 2600' - 100 sx. w/1 sx. F.C. @ 1930' - 40 sx. @ 315' - 10 sx. @ 40' - 15 sx. in Rathole - 10 sx. in Mousehole.

Plugging Proposal Received by: Marion J. Schmidt
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 1:00A.M., Day: 3, Month: January, Year: 92

Actual plugging report: Golden Eagle ordered 200 sx. 60/40 pozmix - 6% gel. - 3% c.c. and 1 sx. flocele. Spotted with drill stem, circulated hole first, heavy mud between all plugs.

1st. plug @ 2600' w/ 25 sx. cement.
2nd. plug @ 1930' w/100 sx. cement with 1 sx. Flocele.
3rd. plug @ 315' w/ 40 sx. cement.
4th. plug @ 40' w/ 10 sx. cement.
15 sx. in Rathole (Circulate) - 10 sx. in Mousehole (Circulate)

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 16 1992

1-16-92

Remarks: Cement by Allied Cement.
Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO WICHITA, KS
Bottom plug(in place): YES , CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 2831 GL

I did not [X] observe the plugging.

Marion J. Schmidt
(agent)

File-S

INVOICED
DATE FEB 07 1992
34438
INV. NO.