

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 153-20,461-0000
C-NW-5N, Sec. 10, T 2 S, R 32 W/E
_____ feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

_____ feet from W/E section line

Operator License # 6063

Lease Name PETTERA Well # A-1

Operator: GEODESSA CORPORATION
Name &
Address 1125 17th St. #2220
DENVER, COLORADO
80202

County RAWLANS
Well Total Depth 4045 feet
Conductor Pipe: Size - feet -
Surface Casing: Size 8 5/8 feet 289

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor ABERCROMBIE DRILL License Number #179

Address 801 UNION CTR. WICHITA, MO. 67202

Company to plug at: Hour: 6:00 AM Day: 18th Month: OCT Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO HAROLD MALEY

(company name) ABERCROMBIE DRILL (phone) 316-262-2841

were: 8 5/8" - 289 FT SP. CUC - 220 FT COMMON - 2% GEL - 3% CA-CL. (BY HALLIBURTON)

ORDER - 180 FT 50/50 Formix 6% GEL - 3% CA-CL. AND 8 5/8" PLUG

SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1st PLUG @ 2610 FT - 20 FT CNT. 2nd PLUG @ 1020 FT - 100 FT CNT.

3rd PLUG @ 300 FT - 40 FT CNT. 4th PLUG ^{SOLID BRIDGE} _{HULLS - PLUG} @ 40 FT - 10 FT CNT.

10 FT RAT HOLE (CIRCULATE)

Signed Maurice Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:30 PM Day: 18th Month: OCT Year: 1982

ACTUAL PLUGGING REPORT 8 5/8" - 289 FT SP. CUC - (BY HALLIBURTON)

ORDERED 180 FT 50/50 Formix 6% GEL - 3% CA-CL. AND 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS

1st PLUG @ 2610 FT - 20 FT CNT. - 2nd PLUG @ 1020 FT - 100 FT CNT.

3rd PLUG @ 300 FT - 40 FT CNT. - 4th PLUG - ^{SOLID BRIDGE} _{HULLS - PLUG} @ 40 FT - 10 FT CNT.

10 FT IN RAT HOLE (CIRCULATE)

Remarks: DID NOT PENETRATE ARBUCKLE

10-26-82
RECEIVED
STATE CORPORATION COMMISSION

OCT 26 1982

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED
DATE 11-15-82
INV. NO. 1593-W

Signed Maurice Schmidt
(TECHNICIAN)