

KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA STATE OFF. BUILDING  
130 S MARKET ROOM 2078  
WICHITA KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-207-22,317  
LEASE NAME Dinius  
WELL NUMBER 40  
<sup>1980</sup>  
~~660~~ Ft. from S Section Line  
~~660~~ Ft. from E Section Line  
SEC. 31 TWP. 24 RGE. 13 (E) or (W)

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Cross Oil LLC  
ADDRESS Box 94 Hamilton KS.  
PHONE# (620) 678-3813 OPERATORS LICENSE NO. 32044

COUNTY Green Wood  
Date Well Completed 9-18-80  
Plugging Commenced 6-25-04  
Plugging Completed 6-25-04  
1:30 P.M.  
(date)

Character of Well Bad  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)  
The plugging proposal was approved on 6-15-04  
by Mike Heffron FIELD Agent (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation Bartlesville Depth to Top 1631' Bottom 1649' T.D. 1715'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Bartlesville</u>	<u>Water</u>					
	<u>Surface</u>	<u>0</u>	<u>40</u>	<u>4 1/2"</u>		<u>Left In</u>
	<u>PRODUCTION</u>	<u>0</u>	<u>1715</u>	<u>4 1/2"</u>	<u>1715</u>	<u>Left In</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
4 1/2" still has a shoe on bottom, well had fiber glass tubing & packer in hole, tubing was into, tried to fish, couldn't get it out, set rock & cement bridge on top of tubing @ 715' 10' of rock, perforated casing @ 700' mixed & dumped 10 sacks of cement, perforated casing again at 150' set 10' rock bridge, consolidated mixed & circulated cement to surface inside & out  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Consolidated Oil Well Services License No. 32044  
Address Box 103 Eureka KS 67045

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Cross Oil LLC

STATE OF Ks COUNTY OF Green Wood, ss.

Dennis Smith (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dennis Smith

(Address) Box 94 Hamilton KS.

RECEIVED  
JUL 21 2004  
KCC WICHITA

SUBSCRIBED AND SWORN TO before me this 7 day of July, 2004

Cynthia L. Hardin  
Notary Public

My Commission Expires: 3-4-2006

CYNTHIA L. HARDIN  
Notary Public - State of Kansas  
My Appt. Expires 3-4-06

Form CP-4  
Revised 05-88

# CONSOLIDATED OIL WELL SERVICES

PO Box 103  
Eureka, Kansas 67045

Cementing Ticket  
and Invoice Number

No. **5568**

Date <b>6-25-04</b>	Customer Order No. <b>2541</b>	Sect.	Twp.	Range	Truck Called Out	On Location	Job Began	Job Completed
Owner <b>CROSS OIL</b>		Contractor <b>Co. Tools</b>			Charge To <b>CROSS OIL</b>			
Mailing Address <b>P.O. Box 94</b>		City <b>HAMILTON</b>			State <b>KS 66853</b>			
Well No. & Form <b>DINIUS #40 INJECTION</b>		Place		County <b>GREENWOOD</b>		State <b>KS</b>		
Depth of Well	Depth of Job <b>150'</b>	Casing	(New) Size <b>4 1/2</b>	Weight	Size of Hole Amt. and Kind of Cement	Cement Left in casing by	Request Necessity _____ feet	
Kind of Job <b>P.T.A. / old well</b>					Drillpipe	(Rotary) Cable	Truck No. <b>445</b>	

Price Reference No.	
<b>5405A</b>	<b>465.00</b>
Price of Job	
Second Stage	
<b>5406</b>	<b>35.25</b>
Mileage <b>157</b>	
Other Charges	
Total Charges	<b>500.25</b>

Remarks **Safety Meeting: Rig up to 4 1/2 casing. (4 1/2 perforated @ 150' below G.L.) Break circulation w/ fresh water. Good fluid returns to surface on annulus of 4 1/2. Spot solid cement plug from 150' to surface on inside of 4 1/2 & on annulus of 4 1/2. = 35 SKS total cement. (class "A" w/ 4% GEL). Job complete. Rig down. 1:30 pm**

Cementer **KEVIN MCCOY**  
 Helper **TROY, JUSTIN** District **EUREKA** State **KS**  
 The above job was done under supervision of the owner, operator, or his agent whose signature appears below.  
**Thank you** **x Called By Dennis Smith**  
Agent of contractor or operator

Sales Ticket for Materials Only

Quantity Sacks	BRAND AND TYPE	PRICE	TOTAL
35 SKS	Regular Class "A" Cement	1104	311.50
2 SKS	GEL 4%	1118	24.80
<b>RECEIVED</b>			
<b>JUL 21 2004</b>			
<b>KCC WICHITA</b>			
Plugs	<b>5407 Ton</b>	Mileage	<b>60.00 M/C</b>
	Delivered by Truck No. <b>439</b>	Sub Total	<b>896.55</b>
	Delivered from <b>EUREKA</b>	Discount	
	Signature of operator <b>Kevin McCoy</b>	Sales Tax	<b>21.19</b>
		Total	<b>917.74</b>

**191076**