



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERSAL PERMIT FORM
(To Be Filled By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 2 1973
CONSERVATION DIVISION
Wichita, Kansas
10-2-73

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. R. L. Sixbury of Murfin Drilling Company has this
date requested permission to plug the following described well:

Mr. Sixbury guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company,

Complete Address: 650 Fourth National Bank Bldg., Wichita, Kansas.

Lease Name: Lewis Well No. C-1

Location: App: -NE-NE-SW Sec. 32 Twp. 2 Rge. (E)(W) 33

County: Rawlins Total Depth 4125' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sixbury was instructed to plug the well as follows:

207'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1700'.

Circulate hole with heavy mud. Pull DP to 1925' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 215' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

W. L. DeChalk
Conservation Division Agent