



15-153-20297-00-00

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 12 1977  
9-12-77  
CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Lowry of Stoepelwerth Drlg. has this  
date requested permission to plug the following described well:

Mr. Lowry guarantees payment of the plugging fee.

Operator's full Name: Edward J. Ackman, Robert Schulein & Assoc.

Complete Address: 811 Denver Center Bldg., Denver, Colo.

Lease Name: Rosie Reuber Well No. 1

Location: NW SE Sec. 18 Twp. 2 Rge. (E)(W) 33

County: Rawlins Total Depth 4320' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Lowry was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 1200' thru drill  
pipe. Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy  
mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Massey  
Conservation Division Agent