

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warrior Inc.

Address: P.O. Box 399 Garden City Ks. 67846

Phone: (620) 272-1023 Operator License #: 4058

Type of Well: Oil EOR Docket #: E-25,280
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 3/26/04 BE 7/16/04 (Date)

by: Herb Deines (KCC District Agent's Name)

Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No

Producing Formation(s): List All (If needed attach another sheet)

Lansing Depth to Top: 3128' Bottom: 3226 T.D. 3345'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-009-22153-00-01

Lease Name: Brenn

Well Number: 4

Spot Location (QQQQ): C - SW - NW - SW

1650' Feet from ☐ North / ☒ South Section Line

4950 Feet from ☒ East / ☐ West Section Line

Sec. 26 Twp. 19 S. R. 11 ☐ East ☒ West

County: Barton

Date Well Completed: 1/5/81 KCC BE 7-16-04

Plugging Commenced: 6/20/04

Plugging Completed: 6/20/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Lansing	oil	3132	3236	85/8	217'	0
				41/2	3344'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 100 sx cement with 500# hulls and pumped down 41/2 casing, Shut in on Vac. Mixed 10 sx cement and pumped down 85/8 casing pressured to 300# and shut in. Topped 41/2 casing off with 20sx. Cut casing off 6' Below surface, back filled and replaced top soil. Cement was 60/40 pos.

Name of Plugging Contractor: Swift Services Inc. Company Tools American Warrior Inc. License #: 32382 99998 **RECEIVED**


Address: P.O. Box 466 Ness City Ks. 67560

Name of Party Responsible for Plugging Fees: American Warrior Inc.

State of Kansas County, Finney, ss.

Jody Smith

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature]

(Address) P.O. Box 399 Garden City Ks. 67846

SUBSCRIBED and SWORN TO before me this 13 day of July, 20 04

[Signature] My Commission Expires: 11/4/07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202 BE