


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

CHEYENNE County. Sec. 14 Twp. 28 Rge. 40W (E) (W)

Location as "NE/CNW/SW" or footage from lines C SE SE
Lease Owner PAN-AMERICAN PETROLEUM COMPANY
Lease Name HAROLD GARMICHAEL Well No. 1
Office Address BOX 591, TULSA, OKLAHOMA
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed APRIL 28, 1963
Application for plugging filed APRIL 29, 1963
Application for plugging approved APRIL 29, 1963
Plugging commenced APRIL 30, 1963
Plugging completed APRIL 30, 5:00 a.m., 1963
Reason for abandonment of well or producing formation DRY HOLE



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ELDON FETTY, HAYS, KANSAS
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5170 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>CLAY, SAND, GRAVEL & BLUE SHALE</u>	<u>SURFACE CASING</u>	<u>-0-</u>	<u>346.85KB</u>	<u>8-5/8"</u>	<u>346.85' KB</u>	<u>NONE</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED HOLE:

Mud from 5170' up to 2100'. Spotted 50 sx. cement through drill pipe by Halliburton.
Mud up to 300'. Spotted 20 sx. cement through drill pipe by Halliburton. Mud up to 40', 1 sk. hulls, Halliburton Plug, 10 sx. cement to cellar zero.

RECEIVED
STATE CORPORATION COMMISSION

MAY 6 1963
5-6-63

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor SIERRA PETROLEUM CO., INC.
Address 208 PETROLEUM BUILDING, WICHITA, KANSAS

STATE OF KANSAS COUNTY OF RUSSELL, ss.
C. T. HONAKER, DRLG. SUPT. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God:

(Signature) C. T. Honaker C. T. HONAKER, DRLG, SUPT.

BOX 232, RUSSELL, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of May, 1963

My commission expires 10-17-63

Leroy Bieby
Notary Public.



15-023-30030-00-00

PAN-AMERICAN PETROLEUM CORP. - Operator
SIERRA PETROLEUM CO., INC. - Contractor

T. D.: 5170'
Elev.: 3394' D.F.

HAROLD CARMICHAEL #1
C SE SE
Sec. 14-2S-40W
Cheyenne County, Kansas

Commenced: 4-14-63
Completed: 4-28-63

Casing:

8-5/8" Set at 346.85' K.B.

Cement:

with 300 sx. Pozmix

FORMATION	DEPTH
Sandy Clay	70
Sand & Gravel	100
Blue Shale	350
Shale	1740
Shale & Shells	2680
Shale & Sand	2860
Shale, Pyrite & Sand	2990
Lime	3035
Shale & Anhydrite	3230
Shale & Red Bed	3350
Shale & Lime	3505
Lime	3547
Lime w/ Shale Streaks	3660
Lime	3713
Shale & Lime	3896
Lime	3908
Lime & Shale	3996
Lime	4300
Shale & Shells	4335
Lime	4465
Lime & Shale	4958
Sandy Lime & Shale	4990
Sand & Lime	5027
Sandy Lime & Shale	5114
Lime	5170

RECEIVED
STATE CORPORATION COMMISSION

MAY 6 1963
5-6-63
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

C. T. Honaker
Drilling Superintendent

Subscribed and sworn to before me this 3rd day of May, 1963.

Jersey Dutz
Notary Public

My commission expires: 10-17-63