

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-023-20,235-00-00

LEASE NAME Pannbacker

WELL NUMBER 1-30 K

SPOT LOCATION C, SW, SE

SEC. 30 TWP. 2 RGE. 37 (X) or (W)

COUNTY Cheyenne

Date Well Completed 6-26-85

Plugging Commenced 6-28-85

Plugging Completed 6-28-85

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Coastal Oil & Gas Corp.

ADDRESS Box 1332, Amarillo, Texas 79189

PHONE # (806) 372-8121 OPERATORS LICENSE NO. 6593

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? _____

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation None Depth to top _____ bottom _____ T.D. 5608

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		Surface	428'	8 5/8	6-20-85	--

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Filled w/mud and Spotted Cement Plugs, #1 3300 - 3270 255 KS, 50-50 Po3, 6% gel, 3% CaCl;

#2, 2400-2050 100 sks 50-50 Po3, 6% gel, 3% CC; #3 427-254, 40 sks 50-50 Po3, 6% gel, 3% CaCl, 10 sks in Mouse Hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Haliburton License No. _____

Address _____

STATE OF _____ COUNTY OF _____, ss.

James E. Adams (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) James E Adams

(Address) Box 1332, Amarillo, Texas

SUBSCRIBED AND SWORN TO before me this 15th day of July, 1985

Sandra K. Frible
Notary Public

My Commission expires: July 25, 1987
Wichita, Kansas



15-023-20235-00-00

SIDE TWO (Page Two)

~~AGO-1 WELL HISTORY~~

OPERATOR Coastal Oil & Gas Corp. LEASE NAME Pannbacker SEC. 30 TWP. 2 RGE. 37 (E) (W)

FILL IN WELL LOG AS REQUIRED: WELL NO. _____

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
T/Stone Corral	3300			
Topeka	4128			
Heebner	4300			
Lansing	4346			
Marmaton	4662			
Ft Scott	4754			
Cherokee Sh.	4808			
Mississippi	5058		Logs	
Arbuckle	5262		CDL &	
Reagan	5040		CNNL/w GR	
<p>DST #1 4724-90' op. 5 min. verk wk blo Rec 10' mud</p>				
<p>IF 4-49#; ISJ 1093# FF 49-49#; FSI 800#</p>				

RECEIVED
STATE CORPORATION COMMISSION

7-17-85

CONSERVATION DIVISION
Wichita, Kansas