

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-023-20233-00-00

LEASE NAME Wilkins

WELL NUMBER 16-7

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 16 TWP. 2S RGE. 37W (E) or (W)

COUNTY Cheyenne

Date Well Completed

Plugging Commenced 9-9-96

Plugging Completed 9-11-96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kansas Corporation Commission

ADDRESS 130 S. Market, Room 2078 Wichita, KS 67202

PHONE# (316) 263-8809 OPERATORS LICENSE NO.

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? if not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4800'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	400'	none
				5 1/2	4793'	3220'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl... were used, state the character of same and depth placed, from feet to feet each s...
Plugged off bottom with sand to 4750' & 5 sks cement. Shot casing @ 3220', came loose. Pulled casing to 2189' & spot 200 sx cement w/200# hulls. Pulled up to 400' and mixed 50 sx cement, circulated to surface. Pulled rest of casing, top off with 10 sx cement. 60/40 10% gel. Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kansas Corporation Commission

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 23rd day of September, 19 96

Irene Herzberg
Notary Public

KANSAS CORPORATION COMMISSION
My Commission Expires:

9-24-1996

