

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: BEAR PETROLEUM, INC.
Address: P.O. Box 483 Haysville, Kansas 67060
Phone: (316) 524-1225 Operator License #: 4419
Type of Well: SWDW Docket #: D-22481
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Jack Luthi (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. 3780'

API Number: 15-155-20,923#00-01
Lease Name: Sleeper 1-30
Well Number: _____
Spot Location (QQQQ): -W2-NW-NW/4
660 Feet from North / South Section Line
330 Feet from East / West Section Line
Sec. 30 Twp. 22 S. R. 9 East West
County: Reno
Date Well Completed: 4-15-84
Plugging Commenced: 7-8-04
Plugging Completed: 7-9-04

KCC
BEM
7-26-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	333'	None
				5-1/2"	3783'	1610'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 2700' and 5 sacks cement. Cut casing loose @1610', pulled up to 1350', pumped 35 sacks cement with 100# hulls, pulled up to 850', pumped 35 sacks cement with 50# hulls, pulled up to 385' and circulated cement to surface. 60/40 pos, 4% gel.

Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524
Name of Party Responsible for Plugging Fees: Bear Petroleum, Inc.
State of Kansas County, Rice, ss.

RECEIVED
JUL 23 2004
KCC WICHITA

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 22nd day of July, 20 04

Irene Herzberg
Notary Public

My Commission Expires: _____

