

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 September 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: RUPE OIL COMPANY, INC.

Address: P.O. Box 783010 Wichita, Kansas 67278

Phone: (316) 689-3520 Operator License #: 5047

Type of Well: Gas Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: (Date)

by: Virgil Clothier (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: Bottom: T.D. 1905'

API Number: 15-053-20,339-00-01

Lease Name: Sunridge Farm LTD.

Well Number: 1

Spot Location (QQQQ): C - NE/4

3960 Feet from North / X South Section Line

1320 Feet from X East / West Section Line

Sec. 17 Twp. 16S S. R. 7 East X West

County: Ellsworth 19

Date Well Completed: 6-11-94 KCC

Plugging Commenced: 6-28-04 BEM 7-26-04

Plugging Completed: 6-29-04

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows show 7" casing to 213' and 4-1/2" casing to 1905'.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Plugged off bottom with sand to 1700' and 4 sacks cement. Perforated 4-1/2" casing @850', 550' & 265', Ran 2" tubing to 850', pumped 35 sacks cement, pulled tubing up to 550', pumped 35 sacks cement, pulled up to 265' and circulated cement to top of 4-1/2" casing & 7" surface. 60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529

Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Rupe Oil Company, Inc.

State of Kansas County, Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly


sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature]

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 22nd day of July 2004

[Handwritten Signature] My Commission Expires: [Handwritten Date]



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED JUL 23 2004 KCC WICHITA

[Handwritten mark]