

KANSAS

M STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-153-20087-00-00

RECEIVED
STATE CORPORATION COMMISSION
OCT 5 1970
CONSERVATION DIVISION
Wichita, Kansas
10-5-70

Operator's Full Name Mack Oil Company,

Complete Address 812 Union Center Building, Wichita, Kansas.

Lease Name David Well No. 1

Location 150' SE of CSE-SE Sec. 1 Twp. 2 Rge. (E) (W)36

County Rawlins Total Depth 3220'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita Plaza, Wichita, Kansas. License No.

Operation Completed: Hour 7:30 PM Day 29 Month 9 Year 1970

The above well was plugged as follows:

309'--8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 2025'.

Circulated hole with heavy mud. Pulled DP to 2250' and displaced 100 Sx. cement thru
DP from 2250' to 1925'. Pulled DP to 315' and displaced 20 Sx. cement thru DP from
315' to 255'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *H. L. Nichols*
Well Plugging Supervisor

DATE 10-5-70

INV. NO. 2619-W