

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-00024-00-00

RECEIVED  
STATE CORPORATION COMMISSION

NOV 10 1961

CONSERVATION DIVISION  
Wichita, Kansas

11-10-61

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Rawlins

Location: NE SE SW Sec. 8 Twp. 2 Rge. \_\_\_\_\_ (E) \_\_\_\_\_ (W) 36

Name of Field: \_\_\_\_\_ Total Depth: 4535

I have this date completed supervision of plugging of:

Lease Name: Kacirek Well No. 1

Operator's Full Name: Miami Pet Co

Complete Address: Box 2040 Abilene, Texas

Plugging Contractor Central Pipe Pulling & Halliburton Co.

Address: Great Bend, Kansas License No. 459

Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X

Other well as hereafter indicated; \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No X

If Yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 2PM Day 6 Month 11 Year 61

The above well was plugged as follows:

8 5/8" 405' circulated with cement - 5 1/2" 4534' cemented. PB to 4360',  
perforated 4224' - filled with sand to 4200', set 4 sax cement dump bailer,  
pulled 1430' 5 1/2" to 410', circulated hole with heavy mud through 5 1/2" ( 24 sax  
Gel), displaced 25 sax cement through 5 1/2" at 410', heavy mud to 35', set  
bridge and 10 sax cement to bottom callar.

Mudding and cementing by Halliburton Co.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks:

INVOICED  
DATE 11/30/61  
INV. NO. 4085-W