

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 30 1961

CONSERVATION DIVISION
Wichita, Kansas

10-30-61

15-153-05134-00-00

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rawlins

Location: NW SE SE Sec. 7 Twp. 2 Rge. _____ (E) _____ (W) 36

Name of Field: _____ Total Depth: 5088

I have this date completed supervision of plugging of:

Lease Name: Brumm Well No. F-2

Operator's Full Name: Miami Pet Co

Complete Address: Box 2040 Abilene, Texas

Plugging Contractor Central Pipe Pulling Co

Address: Great Bend, Kansas License No. 459

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated; _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If Yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 24 Month 10 Year 61

The above well was plugged as follows:

8 5/8" 346' circulated with cement. 5 1/2" 4400' top cement on survey 3320'

PB to 4360' - perf 4234'

Sand to 4220', set 4 sax cement with dump bailer - pulled 1807' 5 1/2" to

500', circulated hole with heavy gel mud through 5 1/2" at 500' - displaced

25 sax cement through 5 1/2" at 350' - heavy mud to 35', set bridge and 10 sax

cement to bottom cellar.

Mudding and cementing by Halliburton Co.

Signed: [Signature]

Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED

DATE 11/1/61

INV. NO. 3966-W