

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-05132-00-00

RECEIVED
STATE CORPORATION COMMISSION

OCT 30 1961
CONSERVATION DIVISION
Wichita, Kansas
10-30-61

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rawlins
Location: SW SW SE Sec. 7 Twp. 2 Rge. (E) (W) 36
Name of Field: _____ Total Depth: 5085

I have this date completed supervision of plugging of:

Lease Name: Brumn Well No. F-1

Operator's Full Name: Miami Pet Co Inc

Complete Address: Box 2040 Abilene, Texas

Plugging Contractor Central Pipe Pulling & Halliburton Co

Address: Great Bend, Kansas License No. 459

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If Yes how long? _____ Reason: _____

Operation Completed: Hour 2PM Day 20 Month 10 Year 61

The above well was plugged as follows:

9 5/8" 338' circulated with cement - 5 1/2" 4600' - top cemet on survey 3245'

PB 4344' - perf 4170' -

Set plug at 4100' - sandto 4050' - set 4 sax cement with dump bailer -

pulled 2190' 5 1/2" to 500', circulated hole with heavy mud through 5 1/2"

(50 sax Gel), displaced 25 sax cement through 5 1/2" at 330', heavy mud to

30', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Halliburton Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 11/1/61
INV. NO. 3964-W