

14
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 3 1961
11-3-61
CONSERVATION DIVISION
Wichita, Kansas

15-153-00027-00-00

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rawlins
Location: NE SE SW Sec. 7 Twp. 2 Rge. _____ (E) _____ (W) 36
Name of Field: _____ Total Depth: 5200

I have this date completed supervision of plugging of:

Lease Name: Brumm Well No. A-1

Operator's Full Name: Miami Pet Co

Complete Address: Box
2211x 2040 Abilene, Texas

Plugging Contractor Central Pipe Pulling Co

Address: Great Bend, Kansas License No. 459

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated; _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If Yes how long? _____ Reason: _____

Operation Completed: Hour 6PM Day 30 Month 10 Year 61

The above well was plugged as follows:

9 5/8" 458' circulated with cement - 5 1/2" 4655' - cement survey shows cement
to 3940' - ~~Perforated~~ Perforated 4170' -
Plugs and sand to 4100', set 4 sax cement with dump bailer, pulled 2195'
5 1/2" to 500', circulated hole with heavy mud through 5 1/2" (37 sax Gel),
displaced 25 sax cement through 5 1/2" at 420', heavy mud to 35', set bridge
and 10 sax cement to bottom cellar.
Mudding and cementing by Halliburton Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 11/9/61
INV. NO. 4027-W