

NOV 21 1986 15-53-20438-00-00

6 030814

API NUMBER 15- NA.

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE, SEC. 18, T 2 S, R 36 W

4620 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050

Lease Name KNAPP Well # 1-18

Operator: KELSO CASING PULLING INC.

County RAWLINS 159.06

Name & Address P.O. Box 347

Well Total Depth 4894 feet

CHASE, KANSAS

Conductor Pipe: Size feet

67524

Surface Casing: Size 8 5/8" feet 516'

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor KELSO CASING License Number 6050

Address AS ABOVE

Company to plug at: Hour: AM Day: 21 Month: 11 Year: 19 86

Plugging proposal received from Bill

(company name) KELSO CASING. (phone)

were: 8 5/8" SET @ 516' w/ 275 SX. 4 1/2" SET @ 4884' w/ 600 SX. PBTD 4494'

PERF. 4216'-22' ORDER SAND & COM. CNT. Pull PIPE ORDER 5 SX

HULLS: 150 SX. ATL 65/35 PER 10/60 2% DICE 1 ALLIED CNT. CO. LA RUE

WATER TRUCKS.

Plugging Proposal Received by Carl Goodnow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11 AM Day: 21 Month: 11 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND ON PBTD @ 4494' TO 4160' w/ 4 SX. COM.

CNT. ON SAND w/ BAILER. SHOTS @ 2510'-2365'-2226'-2103'-2023' & 1901'

RECOVERED 1901' OF 4 1/2" CSG.

MIX. & PUMP DOWN 8 5/8" CSG. 5 SX. HULLS 150 SX. ATL CNT. MIX. MAX. PSI

500# CLOSE IN 150" PLUG COMPLETE

STATE CORPORATION COMMISSION

DEC 8 1986
12-8-86
CONSERVATION DIVISION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-9-86

Signed Carl Goodnow (TECHNICIAN)

INV. NO. 15-525
11-21