

NOV 21 1986 15-153-20425-00-00  
API NUMBER 15- NA

6 030812

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SWNE, SEC. 15, T. 2 S, R. 36 (W) #  
4290 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050

Lease Name FRISBIE Well # 1-15

Operator: KEISO CASING PULLING INC.  
Name & Address P.O. Box 347  
CHASE, KANSAS  
67524

County RAWLINS 154.70  
Well Total Depth 4760 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8" feet 562'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor KEISO CASING License Number 6050

Address CHASE KANSAS

Company to plug at: Hour: PM Day: 21 Month: 11 Year: 19 86

Plugging proposal received from Bill

(company name) KEISO CASING (phone) \_\_\_\_\_

were: 8 5/8 SET @ 562' w/400SX. 4 1/2" SET @ 4760' w/500SX. Tcc 3038'

ORDER SAND & CON. CNT. PULL PIPE ORDER 150SX. ECONOLITE 65/3502  
10% GEL 2% DICE 5SX. HULLS. ALLIED CNT. CO. LARUE WATER TRUCKS.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3: PM Day: 21 Month: 11 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND TO 3900' w/4SX. CON. CNT. ON SAND w/BAILER  
2 SHOTS @ 2480' & 2280 RECOVERED 2280' OF 4 1/2" CSG.

MIX & Pump DOWN 8 5/8" CSG. 100SX. ATL CNT. MIX + 5SX. HULLS PRESSURED  
TO 500\* WHEN HEAD BLEW RETRY WAS THE SAME FLUID REMAINED  
@ SURFACE PLUG COMPLETE w/500\* MAX. PSI NO CHOSE IN.

STATE CORPORATION COMMISSION

Remarks: (If additional description is necessary, use BACK of this form.)  
I did not observe this plugging.

DEC 8 1986 12-8-86  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 12-9-86

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 15527