

1-4
6-100470

22
R

-00-00

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-153-20,794

N2 NE SW /4 SEC. 13, 02 S, 36 W
2310 feet from S section line
3300 feet from E section line

Operator license# 6111

Lease G M T Frisbie well # 1

Operator: N-B Company, Inc.

County Rawlins

Address: P.O. Box 506
Russell, Kansas 67665-0506

Well total depth 4546 feet
Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 427 feet

147.75

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Emphasis Oil Operations License# 8241

Address: Russell, Kansas 67665

Company to plug at: Hour: ??? Day: Month: Year:

Plugging proposal received from: Jack Fox

Company: Emphasis Oil Operations phone:

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 3175 feet with 25 sacks Rat hole: 15 sacks
2nd plug @ 2455 feet " 100 " Mousehole: sacks
3rd plug @ 475 feet " 40 "
4th plug @ 40 feet " Wiper plug & 10 sx.

5th plug @ feet "
Plugging Proposal Received by: David K. Wann

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 1:30 am, Day: 4, Month: January, Year: 1993

Actual plugging report: Hole reported plugged as above.
Order 190 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

RECEIVED
STATE CORPORATION COMMISSION

1-8-93
8 1993

Remarks: Elevation: 3305 GL, Anhydrite depth: 3176 - 3223 feet
Anhy. plug: YES Dakota plug: YES Bottom hole plug in place: NO
Plugged through drill pipe: YES
Did NOT penetrate Arbuckle, cemented by Allied Cementing

INVOICED

I did[] / did not[X] observe the plugging.

DATE 1-25-93
INV. NO. 37241

David K. Wann
David K. Wann P.I.R.T. II
(agent)