

NOV 21 1986

6030816

API NUMBER 15-153-20,344-00-01

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

100' w/c
SE SW, SEC. 7, T 2 S, R 36 W

660 feet from S section line
3400 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6050

Lease Name BRUMM Well # 4
County RAWLINS 149.83

Operator: KEISO CASING PULLING INC.
Name & Address P.O. Box 347
CHASE, KANSAS
67524

Well Total Depth 4610' feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8" feet 277'

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KEISO CASING PULLING INC License Number 6050
Address CHASE KANSAS

Company to plug at: Hour: PM Day: 21 Month: 11 Year: 19 86

Plugging proposal received from Bill

(company name) KEISO CASING. (phone) _____

were: 8 5/8" SET @ 277' w/ 350SX. 4 1/2" SET @ 4569' w/ 525SX. & WAS
SQUEEZED TO TOP OF CEMENT NEAR 550' ORDER SAND & COM CNT. PULL
PIPE. ORDER 5SX. HULLS 150SX. ATL 6S/35 psi 10% GEL 2 DICER ALLIED
CMT. CO. KARUE WATER TRUCKS.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1:PM Day: 21 Month: 11 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND TO 3030' w/ 4SX. COM CNT. ON SAND w/ BAILER
SHOTS (SOLID) @ 2021' - 783' & 530' RECOVERED 530' OF 4 1/2" CSG. WITH
LAST JOINTS SHOWING CNT.

MIX. & Pump Down 8 5/8" w/ 100SX. (SOBBL) ATL CNT. MIX - LOCKED UP
w/ MAX. PSI 1200# & CLOSE IN PSI BLED BACK TO 500# WOULD NOT
BREAK DOWN Plug COMPLETE.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

DEC 8 1986
12-8-86
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 12-9-86
INV. NO. 15523
11-21

Signed Carl Goodrow
(TECHNICIAN)