

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-00298-00-00  
Spot: SWSENW Sec/Twnshp/Rge: 8-8S-17W  
2970 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: TURNER Well #: 1  
County: ROOKS Total Vertical Depth: 3319 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

COND Size: 13.5 feet: 36  
PROD Size: 5.5 feet: 3300 w/800 sxs cmt  
SURF Size: 8.625 feet: 1257 w/550 sxs cmt

*A 10789*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/20/2004 12:00 PM  
Plug Co. License No.: 31720 Plug Co. Name: STEWART WELL SERVICE INC  
Proposal Rcvd. from: DENNIS KIRMER Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered 700 sxs 60/40 pozmix - 10% gel - 600# hulls.  
2 1/2" tubing stuck in the hole at 1210'.  
Fluid level 607'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/20/2004 4:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Stewart Well Service ran in the hole with tubing to 1210' and screwed into 2 1/2" tubing stuck in the hole.  
Perf Tech ran a wireline down tubing to 3230'.  
Allied tied onto tubing and pumped 5 barrels water - pressured to Max. P.S.I. 1500#.  
Perf Tech ran back in hole and perforated a two shot perf at 1850'.  
Allied tied back onto tubing and pumped 500 sxs 60/40 pozmix neat.  
Ordered an additional 200 sxs cement. Left well set two hours.  
Unscrewed tubing at 1210'. Pulled to 1100' - pumped 25 sxs 60/40 pozmix to circulate cement out of 5 1/2" casing.  
Pulled tubing and tied onto 5 1/2" casing with a swedge.  
Pumped 80 sxs 60/40 pozmix to circulate cement out of 8 5/8" casing. Shut in 8 5/8" casing and cement circulated out of 13 1/2" casing.  
All holes standing full.  
Max. P.S.I. 300#.  
Used total of 605 sxs cement.

Perfs:


Top	Bot	Thru	Comments
3305	3319		
3109	3117		

RECEIVED  
JUL 22 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed:   
(TECHNICIAN)

JUL 21 2004

INVOICED  
DATE 7-22-04  
INV. NO. 2005060154

HERNDON DRILLING COMPANY #1 TURNER

8-8-17W  
SW SE NW

Contr. \_\_\_\_\_ County \_\_\_\_\_

E. 1853<sup>RB</sup> Comm. \_\_\_\_\_ Comp. 6-15-51 IP 98 BOPD

ROOKS

PHY POT

Tops	Depth	Datum
HEEB	2970	-1117
BR LM	2980	-1127
LANS	3000	-1147
ARB	3297	-1444
T.O.D.	3319	-1466

Casing  
5" 3299  
DST 3109-17, 1 HR,  
300' S WTR:  
DST 3305-19, 1/2 HR,  
200' OIL CUT MUD  
& 10' FREE OIL  
CO 3319  
SWB 3 BOPH

LONE STAR POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

WADICE

WADICE