

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23656-00-00
Spot: NESWSESE Sec/Twnshp/Rge: 21-13S-17W
366 feet from S Section Line, 800 feet from E Section Line
Lease Name: ROME Well #: 4
County: ELLIS Total Vertical Depth: 3600 feet

Operator License No.: 31385
Op Name: M G OIL INC
Address: PO BOX 162
RUSSELL, KS 67665

PROD Size: 5.5 feet: 3597 w/165 sxs cmt
SURF Size: 8.625 feet: 260 w/165 sxs cmt

\$ 117⁰⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/20/2004 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: CURT COUNTS Company: M.G. OIL, INC. Phone: (785) 735-9405

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 500# hulls.
Caing leaks 900' - 2600' - high fluid level.
Ran wireline to 3585'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/20/2004 10:40 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service ran tubing in hole to 2693'.
Allied tied onto tubing - pumped 100 sxs 60/40 pozmix with 300# hulls mixed in.
Pulled tubing to 1800' - pumped 125 sxs 60/40 pozmix with 100# hulls mixed in to circulate cement into pit.
Pulled tubing and tied onto 5 1/2" casing with a swedge.
Pumped 80 sxs with 100# hulls mixed in.
Max. P.S.I. 500#. S.I.P. 100#.
Tied onto annulus and pumped to Max. P.S.I. 800#. S.I.P. 800#.
Backside was full of cement.

Perfs:

Top	Bot	Thru	Comments
3531	3553		
3289	3340		

RECEIVED
JUL 22 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #17069.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

(14)

INVOICED

DATE

7-22-04

INV. NO.

2005060158

Form CP-2/3


JUL 21 2004

ERNST & STEINLE OIL
OPERATIONS

P.O. BOX 859 #4 ROME 21-13-17W
RUSSELL, KS 67665 366' FSL &
CONTR RED TIGER DRILLING CO. CTY ELLIS 800' FEL, SE/4

GEOL _____ FIELD CATHERINE

ELV 1971 KB SPD 10/18/83 CARD ISSUED 4/5/84 IP P 20 BO & 10 BWPD
1966 GI ARB 3531-3553 OA
API 15-051-23,656



DRLRS	Tops	Depth/Datum
ANH	1187 + 784
B/ANH	1231 - 740
ARB	3528 - 1557
RTD	3600 - 1629

8 5/8 " 260 / 165SX; 5 1/2 " 3597.5 / 165SX
DST (1) 3289-3340 (LKC) / 30-30-30-30, WB, DIED IN 15", REC
20' THIN M., SIP 329-276#, FP 82-80 / 105-112#
DST (2) 3506-60 (PENN) / 45-45-45-45, FB, INCR TO 5 INCH &
REMAINED, 120' GIP, REC 130' HO & GCM, SIP 831-784#, FP
80-96 / 135-124#
MICT - CO, PF (ARB) 3549-53, W / 4 SPF, AC 250G (MA), SWB
LD, SO, PF (ARB) 3544-46, 3531-33, W / 4 SPF, SWB DWN, SO,
NAT, SET 2" TBG AT 3650, POP (GR 31°), P 20 BO & 10 BWPD,
11/4/83

COPYRIGHT 1983
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS