

RECEIVED
JUL 19 2004
KCC WICHITA

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

15-145.008 92-00-00 **WELL PLUGGING APPLICATION FORM**
(PLEASE TYPE FORM and File ONE Copy)

API # NA (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date. *6/05*

WELL OPERATOR White Hawk Oil Company KCC LICENSE # 05163
(owner/company name) (operator's)
ADDRESS P.O. Box 3363 CITY Tulsa

STATE Oklahoma ZIP CODE 74101 CONTACT PHONE # (918) 582-1022

LEASE O.E. Smith A WELL# 1 SEC. 28 T. 22S R. 15 (East/West)

NE - SE - NE SPOT LOCATION/QQQQ COUNTY Pawnee

1650 FEET (in exact footage) FROM S (N) (circle one) LINE OF SECTION (NOT Lease Line)

330 FEET (in exact footage) FROM (E)W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 10-3/4 SET AT 206' CEMENTED WITH 200 SACKS

PRODUCTION CASING SIZE 7" SET AT 3989' CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: (3980.5-3987) (3962-3950) CIBP - 3970'

ELEVATION 1998 T.D. 3992' PBDT 3970' ANHYDRITE DEPTH 950'
(G.L. (K.B.)) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING According to rules and regulations of Corporation Commission and directions of District Representative.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED?

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Art Rolo PHONE# (785) 737-3530 (cel) 434-2916 (H)

ADDRESS 625 S. Plainville City/State Plainville, KS 67663

PLUGGING CONTRACTOR Allied Cementing Co. KCC LICENSE # NA
(company name) (contractor's)

ADDRESS P.O. Box 31, Russell, KS 67665 PHONE # (785) 483-2627

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) as soon as approval is received

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 7/16/04 AUTHORIZED OPERATOR/AGENT: *R Taylor*
(signature)

DRILLER'S LOG

COMPANY: Natural Gas and Oil Corporation and Cities Service Oil Company

CONTRACTOR: Drilling Department of Natural Gas and Oil Corporation

PARK: O. E. Smith "A"-1, NE SE NE Sec 28-228-15W Pawnee County, Kansas

COMMENCED: March 10, 1954 - Rotary
March 31, 1954 - Cardwell

COMPLETED: March 24, 1954 - Rotary
April 3, 1954 - Cardwell

ELEVATION: 1992 RB

0	to	80	Sand
80	to	120	Sand and clay
120	to	350	Shale and shells
350	to	475	Sand
475	to	950	Red bed and shale
950	to	980	Anhydrite
980	to	1675	Shale and shells
1675	to	3415	Lime and shale
3415	to	3419	Shale
3419	to	3495	Lime and shale
3495	to	3531	Shale
3531	to	3541	Lime and shale
3541	to	3770	Lime
3770	to	3935	Lime and shale
3935	to	3955	Shale
3955	to	3966	Sand
3966	to	3980	Shale
3980	to	3990	Arbuckle
		3990	T. D. Rotary
		3992	T. D. Cardwell

RECEIVED
JUL 19 2004
KCC WICHITA

Set 206 feet of 10 3/4" 32# surface pipe. Cemented with 200 sacks cement and 4 sacks calcium chloride.

Set 7" casing at 3989. Cemented with 150 sacks cement.

TOPS:	Anhydrite	950	Lansing	3541	Viola	3681
	Hoebner	3415	Base KC	3775	Simpson	3936
	Brown Ls	3531	Conglomerate	3846 @	sd	3954
					Arbuckle	3980

DRILL STEM TESTS:

- #1- 3543-55, open 1 hr, weak 3 min blow, rec 15' mud, SI 20 min, 100# BHP. G/ IFF and G/ FFF.
- #2- 3956-66, open 1 hr, weak steady blow, rec 120' gas, 65' heavily oil cut mud, SI 30 min, G/ IFF and FFF, 1250# BHP.
- #3- 3980-90, open 1 hr, strong blow, rec 240' gas in pipe, 3240' clean gassy oil, 60' oil and gas out mud, SI 15 min, IFF 210#, FFF 1100#, no BHP, clock stopped.

Ran Schlumberger

Drilled plug and made 2 feet new hole. Hole filled up 2500 feet oil in 5 hours, no water. Set overnight filled up 3600 feet oil, no water. Swabbed 20 BOPH for 2 hours.

April 26, 1954, State Potential 240 BOPD, no water, 38.0 Grav.

C E R T I F I C A T E

I, Claud Shotts, do hereby certify that the above and foregoing is a true and correct copy of the log of the O. E. Smith "A" #1, NE 25 NE Section 28-22S-19W, Pottawatomie County, Kansas, as reflected by files of the Natural Gas and Oil Corporation.


Claud Shotts, Regional Geologist

Subscribed and sworn to before me, a Notary Public, within and for Sedgewick County, Kansas this 30th day of April, 1954.


Esther Russell, Notary Public

My commission expires May 25, 1957.

RECEIVED
JUL 19 2004
KCC WICHITA

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

White Hawk Oil Company
PO Box 3363
Tulsa, OK 74101

July 22, 2004

Re: SMITH O E - A #1
API 15-145-00892-00-00
NESENE 28-22S-15W, 1650 FNL 330 FEL
PAWNEE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888

Sincerely,


David P. Williams
Production Supervisor