

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

RECEIVED  
JUL 21 2004  
KCC WICHITA

FORM CP-1 (1/3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE FILL IN THIS FORM and File ONE Copy)

API # 15-073-23981 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Schankie Well Service, Inc. KCC LICENSE # 6470  
(owner/company name) (operator's)

ADDRESS 1006 SW Blvd, P O Box 397 CITY Madison

STATE Kansas ZIP CODE 66860 CONTACT PHONE # (620) 437-2595

LEASE Huber WELL# 14 SEC. 27 T. 22S R. 11 (East/West)

W2 - E2 - E2 - NE SPOT LOCATION/QQQQ COUNTY Greenwood

1320 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

528 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE NA SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 100' CEMENTED WITH 35 SACKS

PRODUCTION CASING SIZE NA SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: \_\_\_\_\_

ELEVATION 1223 T.D. 2005 PBDT \_\_\_\_\_ ANHYDRITE DEPTH \_\_\_\_\_  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Spot plugs down 3 1/2" Drill Pipe as follows:

15sxs @ 1990', 15sxs @ 868' & 35sxs @ 150' to surface

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? No

If not explain why? No logs were taken, new well that was dry.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Clifford Schankie PHONE# (620) 437-2595

ADDRESS P O Box 397 City/State Madison, Kansas 66860

PLUGGING CONTRACTOR Schankie Well Service, Inc. KCC LICENSE # 6470  
(company name) (contractor's)

ADDRESS PO Box 397 Madison, KS 66860 PHONE # (620) 437-2595

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 6-26-04 Plugged

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 6-26-04 AUTHORIZED OPERATOR/AGENT: Clifford Schankie, Sec  
(signature)

John Barker  
415 E. Jackson St  
Iola, KS 66749  
620-365-7806

# RIG 6 DRILLING COMPANY, INC

2022 S. STATE STREET  
P.O. Box 227  
IOLA, KANSAS 66749

R. K. "Bud" Sifers  
670 Soldier Rd  
Bronson, KS 66716  
620 -365-6294

Company:	Schankie Well Service	Commenced:	6/22/2004
Address:	Box 397	Completed:	June 26, 2004
	Madison, KS 66860	Well #:	14
Lease:	HUber	API #:	15-073-23,981
County:	Greenwood	Status:	Dry Hole
Location:	1320 FNL/ 330 FWL	Total Depth:	2004'-6 3/4"
	27-22-11	Casing:	100'-8 5/8" csg cmt w 35 sx

## Driller's Log:

12	Soil and Clay	1075	Ls
13	LS	1078	Sh
51	Shale	1113	LS w/Sh brks
111	LS w/Sh strks	1250	Sh
244	Sh	1296	LS
280	LS	1311	Sh
342	Sh	1325	LS w/Sh brks
383	LS w/Sh brks	1455	Ls
425	Sh w/LS brks	1585	Sh
436	LS	1616	Ls w/ sh brks
493	Sh	1697	Sh w/ ls brks
501	LS	1797	Ls
565	Sh	1703	LS
580	LS w/Sh brks	1849	Sh w/LS brks
627	Sh	2004	Sh T.D.
632	LS w/Sh brks		
648	Sh		
681	LS w/Sh brks		
877	Sh		
949	Sa		
972	Sh		
1000	Sand		

## PLUG REPORT

6/26/2004

Plug 1230 to 1430 Hrs  
15 sx @ T.D. (50' plug)  
15 sx @868 (Base KC 50' plug  
150' to Surface 35 sx  
Consolidated Cement  
60/40 Pozmix 4% gel  
Consol ticket #5569

RECEIVED  
JUL 21 2004  
KCC WICHITA