



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 25 1963
9-25-63

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Marion Helberg of Empire Drilling Co., has this

date requested permission to plug the following described well:

Mr. Helberg guarantees payment of the plugging fee.

Operator's full Name: Empire Drilg. Co., & Time Petr. Co.,

Complete Address: 650 4th Nat'l Bank Bldg., Wichita, Kans.

Lease Name: Knapp Well No. 1

Location: NE-SW-NE Sec. 18 Twp. 2 Rge. (E) (W) 36

County Rawlins Total Depth 4880 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Helberg was instructed to plug the well as follows:

3 29' -- 8 5/8" Surface pipe -- cement circulated with 200 Sx.

Circulate hole with heavy mud, set plug @ 660' and 20 Sx cement.

"	"	325'	with $\frac{1}{4}$ sk. hulls &
			20 Sx cement.
"	"	40'	with $\frac{1}{2}$ sk. hulls &
			10 Sx cement.

Very truly yours,

H. L. Nichols
 Conservation Division Agent