



15-153-20087-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 5 1970

CONSERVATION DIVISION
Wichita, Kansas

10-5-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Walter Oden of Red Tiger Drilling Company, has this date requested permission to plug the following described well:

Mr. Oden guarantees payment of the plugging fee.

Operator's full Name: Hack Oil Company,

Complete Address: 812 Union Center Building, Wichita, Kansas.

Lease Name: David Well No. 1

Location: 150' SE of CSE-SE Sec. 1 Twp. 2 Rge. (E)(W) 36

County: Rawlins Total Depth 3220' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Oden was instructed to plug the well as follows:

309'---8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 2025'.

Circulate hole with heavy mud. Pull DP to 2250' and displace 100 Sx.
cement thru DP. Pull DP to 315' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

W. L. Dickels
Conservation Division Agent