

11-27-87

6 070618

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 023-20,250-00-00
SW NW, SEC. 21, T 2 S, R 37 W/E
2970 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4528
Operator: Paul Prijatel
Name & Address: 201 West 8th Street #450
Pueblo, Colo 81003

Lease Name Glasco Well # 21-4
County Cheyenne 156.00
Well Total Depth 4800 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 363

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A

Other well as hereinafter indicated _____

Plugging Contractor Golden Eagle Drilling License Number 1475

Address Box 983 McCook, Ne 69001

Company to plug at: Hour: 1:00 AM Day: 27 Month: Nov Year: 19 87

Plugging proposal received from Dave Prijatel

(company name) Paul Prijatel (phone) _____

were: 8 5/8" 363' S.P. cwc w/250 sks 60/40 Pozmix 2% Gel 3% Ca Cl By B. J. Titan

Elevation 3387' Anh 3201' No circulation problems, mud condition. Weight 9.4 Viscosity 57 Water Loss 8.6. Proposal 210 sks 60/40 Pozmix 6% Gel 3% Ca Cl and 8 5/8" plug.

Spot with drill stem recondition hole, mud between all plugs, 25 sks at 3220'; 100 sks at 2520'; 50 sks at 400'; 10 sks at 40'; 15 sks rat hole 10 sks mouse hole. Circulate.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 1:00 AM Day: Nov Month: 27 Year: 19 87

ACTUAL PLUGGING REPORT Ordered 210 sks 60/40 Pozmix 6% Gel 3% Ca Cl and 8 5/8" plug.

Spotted with drill stem Reconditioned hole. Mud between all plugs.

1st plug 25 sks at 3220 ft. 2nd plug 100 sks w/1 sk Flocele at 2520'

3rd plug 50 sks at 400'. 4th plug 10 sks Hulls plug at 40'.

15 sks rat hole circulate 10 sks mouse hole, circulate Cemented by Halliburton

12-15-87
DEC 15 1987
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 12-15-87
INV. NO. 19295
11-27 JAN 14 1988

Signed Marion J. Schmidt (TECHNICIAN)

Marion J. Schmidt FORM CP-2/3 LR
Rev. 01-84