

4-032172

5  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

9-11

API Number: 15-023-20,233-00-00  
180' N. 30' E. of  
SW NE /4 SEC. 16, 02, 37 W  
3480 feet from S section line  
1950 feet from E section line

Operator license# - Lease: Wilkens Well # 16-7

Operator: State of Kansas Fee Fund County: Cheyenne

Address: 2301 E. 13th Street - Dist.#4 Well total depth 4800 feet  
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 400 feet

Aband. oil well X, Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Mike's Testing & Salvage License# 31529

Address: Chase, Kansas 67524

Company to plug at: Hour: P.M. Day: 11 Month: September Year: 1996

Plugging proposal received from: Carl Goodrow - District #4 Staff

Company: State of Kansas Phone: 913-628-1200

Were: Order 350 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Allied Cement Company.  
Order 5 sxs common cement.  
Order sand.

KANSAS RECEIVED  
OCT-2 1996  
A 12:51

10-2-1996

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[ X ], Part[ ], None[ ]

Completed: Hour: 3:45 P.M., Day: 11, Month: September, Year: 1996

Actual plugging report: 8 5/8" set at 400' cwc. 5 1/2" set at 4793' with 265 sxs. Port collar at 3220' unused. Prod. perf. 4624' - 4710'. PBTD 4750' w/wireline. Sand back to 4500'. Dump 5 sxs common cement on sand with bailer. One shot free pipe at 3236'. Pulled casing to 2200' - mixed and pumped 200 sxs cement blend with 500# hulls mixed in, cement circulated into cellar. Pulled casing to 450' - circulated cement to surface with 50 sxs cement blend. Pulled casing - topped off 8 5/8" with 10 sxs cement blend. Used total of 260 sxs cement blend and 500# hulls. Plug complete.

Remarks: \_\_\_\_\_

Condition of casing(in hole): GOOD X BAD \_\_\_\_\_ Anhy.plug: YES X NO \_\_\_\_\_

Bottom plug(in place): YES X, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES X, NO \_\_\_\_\_

Plugged through TUBING \_\_\_\_\_, CASING X. Elevation: \_\_\_\_\_ GL

I did[ X ] / did not[ ] observe the plugging.

Carl Goodrow  
(agent)

10