

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-20840-00-00  
Spot: NWSE Sec/Twnshp/Rge: 32-29S-33W  
1980 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: BLAIR - WILLIAMS Well #: 1-32  
County: HASKELL Total Vertical Depth: 5638 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS, INC. OF KANSAS  
Address: PO BOX 8647  
WICHITA, KS 67208

MSCC Size: feet: 3043  
PROD Size: 4.5 feet: 5500 WITH 165 SX CMT  
SURF Size: 8.625 feet: 1684 WITH 725 SX CMT

\$183<sup>24</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/09/2004 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 5300' & 4 SX CMT. PLUG AT 1710' WITH 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT. 15 SX GEL FOR SPACER.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/09/2004 12:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 5417'. CMT RETAINER AT 5470', 5422', 5417'. SAND BOTTOM TO 5320' & 4 SX CMT ON TOP. 1ST PLUG PULL OUT OF HOLE WITH 4 1/2" TO 1715'. PUMP 15 SX GEL & 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 600'. LOAD HOLE & PUMP 40 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 15 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5376	5408		

RECEIVED  
JUL 23 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1780' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED  
JUL 14 2004  
KCC Dodge City

Signed

Jim Holland  
(TECHNICIAN)

INVOICED  
DATE 7-23-04  
INV. NO. 2005060179

Form CP 273