

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-21018-00-00  
Spot: NESW Sec/Twnshp/Rge: 35-30S-33W  
1980 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: SIMPSON Well #: 3-35  
County: HASKELL Total Vertical Depth: 5693 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS, INC. OF KANSAS  
Address: PO BOX 8647  
WICHITA, KS 67208

PROD Size: 4.5 feet: 4770 WITH 125 SX CMT <sup>5690</sup>  
SURF Size: 8.625 feet: 1702 WITH 500 SX CMT <sup>KCC BEM #184 7-23-04 93</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/14/2004 11:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND BOTTOM TO 4560' WITH 4 SX CMT. PLUG AT 1730' WITH 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/14/2004 2:30 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 4720'. SAND BOTTOM TO 4560' WITH 4 SX CMT ON TOP. 1ST PLUG PULL OUT OF HOLE TO 1730'. LOAD HOLE WITH GEL & PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 600'. LOAD HOLE & PUMP 40 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 15 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
4628	4651		

RECEIVED  
JUL 23 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2470' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland  
(TECHNICIAN)

INVOICED  
DATE 7-23-04  
INVOICE NO. 2005060179

[Signature]