

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-10115-00-01  
Spot: SENE Sec/Twnshp/Rge: 22-28S-34W  
3300 feet from S Section Line, 660 feet from E Section Line  
Lease Name: HUGHES A Well #: 1  
County: HASKELL Total Vertical Depth: 1515 feet

Operator License No.: 32800  
Op Name: NEWFIELD EXPLORATION MID-CONTI  
Address: 110 W. 17TH STREET, SUITE 1300  
TULSA, OK 74119

PROD Size: 4.5 feet: 1514 WITH 350 SX CMT  
SURF Size: 8.625 feet: 808 WITH 425 SX CMT

*#419<sup>24</sup>*

Well Type: SWD UIC Docket No: D17468.0 Date/Time to Plug: 07/19/2004 10:30 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: FILL WITH CMT FROM TOP TO BOTTOM. PRESSURE CHECK.

Plugging Proposal Received By: JIM HOLLAND Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/20/2004 11:00 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 1504'. PUMP 300# HULLS WITH 95 SX CMT. DID NOT PRESSURE. FLUID LEVEL AT 400' & FALLING. SHUT DOWN AND LET CMT SET UP OVERNIGHT. TAG CMT AT 540'. PUMP 35 SX CMT DOWN 4 1/2", FILL FROM 540' TO SURFACE. PRESSURE TO 1000 PSIG & SHUT IN. BACKSIDE FULL.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 1230 | 1340 |      |          |

RECEIVED  
JUL 23 2004  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED  
JUL 20 2004  
KCC Dodge City

Signed

*Jim Holland*  
(TECHNICIAN)

INVOICED  
DATE 7-23-04  
INV. NO. 2005060178

Form CP-2/3