

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-10121-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 17-34S-25W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: W W HAMILL Well #: 1
County: CLARK Total Vertical Depth: 5792 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E. CENTRAL, SUITE 300
WICHITA, KS 67206

PROD Size: 5.5 feet: 5792 WITH 150 SX CMT
SURF Size: 8.625 feet: 1403 WITH 300 SX CMT

#188²⁴

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/19/2004 1:40 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAAS Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: PLUG AT 1450' WITH 50 SX CMT. PLUG AT 400' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT. 15 SX GEL FOR SPACER.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/19/2004 3:10 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

SAND TO 5650' WITH 5 SX CMT. 1ST PLUG PULL TO 1450' & SPOT 15 SX GEL & 50 SX CMT. 2ND PLUG PULL TO 400' & SPOT 40 SX CMT. 3RD PLUG PULL TO 40' & SPOT 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
5711	5728		

RECEIVED
JUL 23 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2100' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed: _____

(TECHNICIAN)

INVOICED

DATE 7.23.04

INV. NO. 2005060176

Form CP-28